


COUNTY ROAD COMMISSIONS

The road improvement process
from start to finish



CHIPPEWA COUNTY ROAD COMMISSION




- 2,045 miles of roads
- 527 lane miles of roads under contract with MDOT
- \$8,900,000 MTF
- 16 townships



GENESEE COUNTY ROAD COMMISSION

- over 1,600 miles of roads
- 811 lane miles of roads under contract with MDOT
- \$40,000,000 MTF
- 17 townships






PLANNING

- PASER/Community Priority Projects
- Programming Project Estimate
- Public Hearings
- Seek Funding
- Job Authorization (External/Internal)
- NEPA/SHPO Permits

DESIGN



DESIGN BIDDING

- Out to Bid
- RFI
- Addendum
- Low Bid
- Bids Over 10% Engineers Estimate
- Bid Awarded (or not!)

**THIS IS WHERE
YOU COME IN!**


CONSTRUCTION

- Pre-Construction Meeting
 - Contractor's **REQUIRED** Submittals
 - Schedule
 - Material Source List (w/ Buy America)
 - Subcontractors
 - Safety Program
 - Staging Area
 - On-The-Job Training
 - Jobsite Postings
 - Contractor Info
- Utility Coordination/Onsite Meeting
- Contract Completion Date



CONTRACT MODIFICATION

- Negotiated Prices Must Be Documented (emailed)
- Don't forget Markup of Subcontractor Items
- Review and Sign (21 days)



Contract Modification

04/27/2022 7:30 AM
FieldManager 5.3c

Contract: 25000-207889, Construction of a roundabout includes hot mix asphalt and co

Cont. Mod. Number	Revision Number	Cont. Mod. Date	Electronic File Created	Net Change	Awarded Contract Amount
1	1	04/27/2022	Yes	\$27,511.88	\$2,239,360.64

Route	Managing Office	District	Entered By
	Genesee County Road Commission	04015	Gerrad A Godley

Contract Location
Grand Blanc Road from Dort Highway (M-54) to the west city l

Short Description
Substitutions, Additional, and Balancing of Items

Description of Changes

A. Original Awarded Contract Amount	\$2,239,360.64
B. Current Net Total Contract Amount	\$2,266,872.52
C. Current Net Total Difference	\$27,511.88
D. Total Net Percentage Change	1.23%
E. MDOT Oversight	
F. Tier 1 - MDOT TSC Approval	


Increases / Decreases

Item Description	Item Code	Prop. Line	Proj. Line	Project	Catg.	Item Type	Quantity Change	Unit	Unit Price	Dollar Value
Aggregate Base, Modified	3027001	0180	0180	207889A	0001	Original	-4,000,000	Ton	26.00000	\$-104,000.00
<p>Reason:</p> <p>A. Replaced 21AA Limestone with 21AA Crushed Asphalt.</p> <p>B. Contractor requested the change for a cost savings to the project; Engineer verified that there was no waters of the state within the required influence of the project.</p> <p>C. Yes, this item replaced the original Maintenance Gravel, Modified item.</p> <p>D. No, item of work will not impact the contract time or open to traffic date(s).</p> <p>E. Changed Conditions.</p> <p>F. Alina Sokolowski, MDOT LAP Representative.</p> <p>G. Contractor provided reduced cost savings to the project.</p> <p>H. See supporting documentation in PW.</p>										
Conc Pavt, Misc, Nonrein, 4 inch	6027011	0700	0630	207889A	0001	Original	-0.150	Syd	30.00000	\$-4.50
Curb and Gutter, Conc, Det B1, Modified	8027001	0810	0730	207889A	0001	Original	-0.490	Ft	20.00000	\$-9.80
Dr Structure Cover, Adj, Case 2, Modified	4037050	0510	1440	207889A	0001	Original	-3.000	Ea	450.00000	\$-1,350.00

Contract: 25000-207889
Cont. Mod.: 1, Rev. 1
Page 1 of 14

PAY ESTIMATE

- Material Certs
 - Material Tickets
 - Contract Mods
- need to be
Approved by
MDOT



Michigan Department of Transportation

Construction Pay Estimate Report

05/11/2021 2:02 PM
FieldManager 5.3c

Contract: 25000-130618, Hot mix asphalt reconstruction of a roundabout, aggregate

Estimate Date	Estimate No.	Entered By	Estimate Type	Electronic File Created	All Contract Work Completed	Construction Started Date
05/11/2021	2	Gerrad A Godley	Semi-Monthly	Yes	06/01/2021	04/12/2021
Prime Contractor Zito Construction			Managing Office Michigan Department of Transportation			
Comments Payment for Mobilization, Culvert, Curb and Pavement Removals						

Pre-Voucher Summary

Project	Voucher No.	Item Payment	Stockpile Adjustment	Dollar Amount
130618A, Hot mix asphalt reconstruction of a roundabout, aggregate ba	0002	\$56,279.65	\$0.00	\$56,279.65
Total Estimated Payment:				\$56,279.65

(Does not include central office adjustments)

Item Usage Summary

Item Description	Item Code	Prop. Line	Project	Category	Project Line No.	Item Type	Mod. No.	Quantity	Dollar Amount
_ Pavt, Rem, Modified	2047011	0060	130618A	0001	0060	00	000	5,839.930	\$29,199.65
Curb, End, Rem, Less than 24 inch	2030005	0030	130618A	0001	0030	00	000	2.000	\$1,000.00
Curb, Rem, Less than 24 inch	2030001	0020	130618A	0001	0020	00	000	5.000	\$1,500.00
Curb and Gutter, Rem	2040020	0050	130618A	0001	0050	00	000	605.000	\$3,025.00
Mobilization, Max \$83,900.00	1500001	0010	130618A	0001	0010	00	000	0.250	\$20,650.00
Total Estimated Item Payment:									\$56,279.65

Estimate Certification

I certify the items included on this report constitute my estimate of work completed and due the contractor as of the date of this document. I also certify the prime contractor is meeting all requirements for minority percentages and the payrolls are current.

Gerrad Godley, PE (Project Engineer) and/or

(Date)

Keith Brown, PE (Construction Engineer)

(Date)

Contract: 25000-130618
Estimate: 2
Page 1 of 1

ROAD COMMISSION + CONTRACTOR

PARTNERSHIP / TEAM

- Understanding Contractor Operations
- Every Road Commission is Different
- How can we Work Together?





***LET'S HAVE A
DISCUSSION...***